240

MYSORE DIVISION.

The 4th January 1896. [ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 25th January 1896, for restoring the Vadayankere tank, Registered No. 40, Nanjangud Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 28th February 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Vadayankere tank, Registered No. 40, Nanjangud Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

DETAILED ABSTRACT ESTIMATE.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork raising bund	C. yd.	6,750
Do breach filling	"	6,073
Excavation for dwarf wall	"	39
Brick in surki do	C. ft.	1,800
Old stone work	C. yd.	189
New stone work	"	1,743
Bench mark stones	Each.	2
Grade stones	"	18
Gauge stone	"	1
Tank No. stone	"	1
Clearing jungle	Lump sum.	
Turfing front slope	C. yd.	106·26
Sluices—		
Constructing a tank sluice	Lump sum.	
Waste weirs—		
Left weir 150′ long.		
Excavation	C. yd.	304
Brick in ordinary mortar	C. ft.	2,680
Plastering with surki mortar	Sqr.	6·46
Stone slabs	C. ft.	170
Rough stone sujikat	C. yd.	351
Pointing with surki mortar	Sqr.	1·80
Clearing silt and excavating draft channel	Lump sum.	
Right weir 150′ long.		
Excavation	C. yd.	393
Brick in mortar	C. ft.	2,680
Plastering with surki mortar	Sqr.	6·46
Burnt stone slabs	C. ft.	170
Rough stone work dry	C. yd.	351
Pointing with surki mortar	Sqr.	1·80
Clearing site and excavating draft channel	Lump sum.	
Distribution—		
Excavating a distributary channel	Ditto	
Constructing distribution sluices	Ditto	
Constructing aqueduct across the right waste weir nala	Ditto	

J. H. KARVE, *Executive Engineer.*